CONCORD SCHOOL DISTRICT

School Administrative Unit #8

Donna PalleyAssistant Superintendent

Christine C. Rath Superintendent Michele M. Croteau Business Administrator

Robert Belmont
Director of Student Services

T. Matthew CashmanDirector of Facilities and Planning

Larry PrinceDirector of Human Resources

March 26, 2012

Ms. Kimberly Tisa PCB Program Coordinator US Environmental Protection Agency, Region 1 5 Post Office Square, Suite 100 Boston, MA 02109-3912

Reference: PCB Abatement Plan

Conant School, Concord, NH

Dear Ms. Tisa:

In accordance with the regulations at 40 CFR 761.61(a)(3) for Self-Implementing Cleanup and Disposal of PCBs, the following attached PCB Abatement Plan has been prepared for the Conant School in Concord, New Hampshire. Plans are to demolish the existing structure to be used as a parking lot. In preparation for demolition, samples of various building materials were tested for PCBS. PCBs greater than 50 parts per million were detected in window caulking and white paint in Addition #3 of the building.

All sampling plans, sample collection procedures, sample preparation procedures, extraction procedures, and instrumental/chemical analysis procedures used to assess or characterize the PCB contamination at the cleanup site, are on file with the School District at 38 Liberty Street, Concord, NH, and are available for EPA inspection.

If you have any questions concerning this data, please do not hesitate to give me a call.

Very truly yours,

Matthew Cashman

Director of Facilities Planning

Concord School District

Attached: PCB Abatement Plan-Conant School

I Chura

Polychlorinated Biphenyl Abatement Plan

For the Site:

Conant Elementary School 152 South Street Concord, NH. 03301

Prepared for:

Town of Concord, NH

C/o Universal Environmental Consultants 12 Brewster Road Framingham, MA. 01702

Prepared by:

Lord Associates, Inc. 1506 Providence Highway, Suite 30 Norwood, MA 02062

Project No. 1808

March 22, 2012

Table of Contents

1.0 Introduction:	
1.1 Purpose & Background:	1
1.2 Contact Information:	
2.0 Site Description:	2
2.1 Building Description	
2.2 Land Use and Surrounding Receptors:	2
2.3 Nature and Extent of PCB Contamination:	2
3.0 Abatement Plan:	4
3.1 Plan Objectives:	4
3.2 Work Plan:	4
3.2.1 PERMITS AND COMPLIANCE:	5
3.2.2 WORK AREA PREPARATION:	
3.2.3 REMOVAL OF PCB MATERIALS:	5
3.2.4 EQUIPMENT AND AREA DECONTAMINATION:	
3.3 Schedule:	7
3.4 Quality Control and Assurance Plan:	
3.4.1 Post Abatement Verification Sampling:	
3.4.2 Laboratory Methods & Associated QA/QC	7
3.5 Contingency Plan:	
4.0 Remedial Waste Management:	8
5.0 Maintenance and Monitoring:	9
6.0 Notifications and Public Involvement:	9

Attachments

Tables

Table 1. Summary of PCB Testing in Building Materials and Soil

Table 2. Summary of Building Materials to be Removed

 Table 3. Laboratory Quality Control Parameters

Figures

Figure 1. Site Locus

Figure 2. Site Plan

Appendices

Appendix A. Photographs

Appendix B. Copy of Original Laboratory Reports

Appendix C. Copy of EPA Standard Operating Procedures for Sampling Porous Surfaces for PCBs

1.0 Introduction:

1.1 Purpose & Background:

Pursuant to 40 CFR 761.61(a)(3) of the Toxic Substances Control Act (TSCA), Lord Associates, Inc. (LAI) is submitting this Polychlorinated Biphenyl (PCB) Abatement Plan for the site referred to as the Conant Elementary School in Concord, New Hampshire (the "Site"). The need for the Abatement Plan was triggered by the identification of PCBs in exterior window caulking and paint on an exterior wood door in preparation of a planned building demolition of the school.

The Site is located within a suburban residential neighborhood located in Concord, New Hampshire. The property on which the Site is located is currently used as an elementary school serving grades K-5. A Site Locus is presented in **Figure 1**.

In planning for the demolition of the building, the Town contracted with Universal Environmental Consultants (UEC) of Framingham, Massachusetts to collect representative samples of existing window/door caulking, paint and adjacent building materials for the analyses of PCBs. According to the Assessor's Office records, the present structure was built in 1929. Concentrations in excess of 50 milligrams per kilogram (ppm) were detected in two materials sampled; the white paint on the exterior front door trim and the exterior window caulking of Addition #3 only (refer to the floor plan, Figure 2).

The Abatement Plan proposes to remove all windows, doors, and associated trim with PCB containing caulking and paint from (only) building Addition #3 for off-site disposal as a "bulk-product waste". It is the position of the Concord School District that building materials identified in the original building that have concentrations of PCBs <50 ppm meet the definition of "Excluded PCB products" as defined at 40 CFR 761.3. It is likely that paint applied to these parts of the building with PCBs were in-place prior to October 1, 1984, and were not derived from or diluted from paint with PCB concentrations greater than 50 ppm identified on Building Addition #3. This conclusion is supported by the following:

- The interior ceiling paint appears different in color than the exterior paint used on Addition #3.
- Exterior paint would not be used as interior ceiling paint due to the finish.
- School maintenance personnel do not recall the ceilings in the original building ever having been painted for at least the 20 years they have been employed.
- In 2005/6 the exterior trim of the school was painted with one coat of paint which would make all exterior paint appear similar.

1.2 Contact Information:

The following information pertinent to the persons assuming responsibility for conducting the Abatement Plan (i.e., the Potentially Responsible Party, PRP) is provided as follows:

PRP Contact Information:

Name: Concord School District, c/o Matt Cashman

Lord Associates, Inc.

Page 1 of 9

Address: 38 Liberty Street,

Concord, NH. 03301

Relationship: Director of Facilities & Planning

Environmental Consultants/Licensed Site Professional Information:

Name: Ralph J. Tella, Lord Associates, Inc.

LSP#: 7473

Address: 1506 Providence Highway, Suite 30, Norwood, MA.

Telephone: (781) 255-5554 x14

2.0 Site Description:

2.1 Building Description

The Conant School is a one-story brick veneer and wood structure of approximately 57,000 square feet. Built in 1929, it has always been used as a school. Five additions to the original building were made: Addition #1 in 1940, Addition #2 in 1961, Addition #3 in 1966, Addition #4 in 1985, and Addition #5 in 1990.

A small grass-covered strip of land is located in the front of the building and east side. Behind the school to the south and west, the area surrounding the building is paved (see Photographs in **Appendix A**).

2.2 Land Use and Surrounding Receptors:

The property on which the School is located is within a primarily residential neighborhood along South Street. The School provides classroom education from kindergarten through grade 5. Potential receptors include students, visitors, faculty and staff. There are no adjacent surface water bodies, wetlands, or critical wildlife habitats.

2.3 Nature and Extent of PCB Contamination:

Representative samples of paint and caulking were collected by RPF Associates, Inc. on February 23, 2010, and by UEC on August 10, 2011 and February 29, 2012. The samples were collected manually by cutting or chiseling, and placed in plastic bags for transport to the laboratory. EMSL Analytical, Inc. laboratory extracted the samples via EPA Method 3540C and analyzed them by EPA Method 8082. A summary of these results is presented in **Table 1**. Copies of the lab reports are provided in **Appendix B**.

These results indicate that PCBs in the form of Aroclor 1254 are present at concentrations greater than 50 milligrams per kilogram (mg/kg), or roughly parts per million (ppm) in white-colored paint on an exterior wood door frame, and in exterior window caulking in Building Addition No. 3.

Lord Associates, Inc. Page 2 of 9

Other detections were recorded on samples of exterior white paint used on the original building front wood columns (5.3 ppm), and in white ceiling paint in Classroom #5 located in the original building (1.1 & 1.7 ppm). Care was taken to collect the paint samples after the surface was cleaned. Samples of ceiling paint from other classrooms located within the original building (Rooms 4 & 9) did not have detectable concentrations of PCBs.

To determine if the PCBs in the exterior window caulking and/or white painted trim had leached into the adjacent building materials and soil, samples of adjacent brick were collected by UEC on November 22, 2011 by manual chiseling. Three soil samples from underneath the window jambs on the north side of Addition #3 were collected by UEC on February 29, 2012 with a hand trowel to a depth of approximately 0-3". See **Figure 2** for the locations of these samples. The samples were extracted via EPA Method 3540C and analyzed via EPA Method 8082 by EMSL Analytical, Inc. These results indicate that *no* PCBs were present at the lab detection limit. A summary table of these results follows. Copies of the original lab reports are provided in **Appendix B**.

Table 1
Summary of PCB Testing in Building Materials & Soil
Mg/Kg, dry weight

Sample ID	Material	Location	Aroclor 1254
022310-B01	Caulk	Southwest entry door in	< 0.99
		hallway, interior	
022310-B02	Caulk	South entry door in Room 2	< 0.99
022310-B03	Caulk	Southwest entry door in	<0.99
		hallway, exterior	
022310-B04	Caulk	Old section bathroom sinks	0.95
022310-B05	Caulk	Tan, hallway across from	2.0
		Room 16 at building seam	
022310-B06	Paint Chip	White, Boiler Room wall	< 0.96
022310-B07	Paint Chip	Grey, Boiler Room Stairs	<1.0
1-8/10/11	White paint on wood	Main Entrance-Original Bldg,	5.3
	-	wood columns	
2-8/10/11	White paint on wood	Addition #2; wood window	< 0.5
	-	column	
3-8/10/11	White paint on wood	Original Bldg-side entrance	< 0.5
4-8/10/11	White paint on wood	Addition #3; front door frame	96
5-8/10/11	White paint	Classroom #5 ceiling	1.1
6-8/10/11	White paint	Radiator Shield; c'rm#7	< 0.5
7-8/10/11	Horizontal. Window	Orig. bldgrear	< 0.5
	frame caulking		
8-8/10/11	Old door front caulking	Orig. bldgrear	<0.5
9-8/10/11	Vertical window front	Orig. bldgrear	<0.5
	caulking		
10-8/10/11	Window frame caulk	Orig. bldgside entrance	<0.5

Lord Associates, Inc. Page 3 of 9

11-8/10/11	Top layer of caulk on old	Orig. bldgMain entrance;	<0.5
	caulk	between wood column and	
		brick	
12-8/10/11	Old caulk	Orig. bldgMain entrance;	<0.5
		between wood column and	
		brick	
13-8/10/11	Window frame caulk	Addition #3	220
1-11/22/11	Brick	Addition #3; North Window	<0.5
		frame	
2-11/22/11	Brick	Addition #3; North Window	<0.5
		frame	
3-11/22/11	Brick	Addition #3; North Window	<0.5
		frame	
1-2/29/12	White Paint	Classroom #5 ceiling	1.7
2-2/29/12	White Paint	Classroom 4 ceiling	< 0.49
3-2/29/12	White Paint	Classroom 9 ceiling	< 0.70
4-2/29/12	Soil	Addition #3, north side	< 0.076
5-2/29/12	Soil	Addition #3, north side	<0.076
6-2/29/12	Soil	Addition #3, north side	<0.068

3.0 Abatement Plan:

3.1 Plan Objectives:

The objectives of this Abatement Plan are to properly remove all materials identified as PCB containing bulk product material for off-site disposal prior to building demolition. This includes all of the exterior windows, doors, and associated white painted frame trim of building Addition #3. These materials will be removed in their entirety (i.e., glazing and windows will not be separated).

Table 2
Summary of Building Materials to be Removed

Item	#	Location
Doors, single	4	Building Addition #3
Double door w/windows	1	Building Addition #3
Window Unit, Large	19	Building Addition #3
Window Unit, Small	3	Building Addition #3

3.2 Work Plan:

Lord Associates, Inc. Page 4 of 9

3.2.1 PERMITS AND COMPLIANCE:

- A. The Contractor shall assume full responsibility and liability for compliance with all applicable Federal, State, and local laws, rules, and regulations pertaining to Work practices, protection of Workers, authorized visitors to the site, persons, and property adjacent to the Work.
- B. Perform PCB related Work in accordance with EPA Regulations at 40 CFR 761.1 (Toxic Substances Control Act), NHDES Hazardous Waste Regulations Chapter ENV-HW-400, OSHA Regulations at 29 CFR 1910.1000, as specified herein. Where more stringent requirements are specified, adhere to the more stringent requirements.
- C. The Contractor must maintain current certificates of training, licenses or registrations pursuant to OSHA, NHDES and EPA regulations for all Work related to this Project, including the removal, handling, transport, and disposal of hazardous and industrial waste.
- D. The Contractor shall be prepared to obtain an EPA ID number if so directed by the Owner.

3.2.2 WORK AREA PREPARATION:

- A. PCB caution signs shall be posted at all approaches to the PCB Work Area. Post all emergency exits as emergency exits only on the Work Area side, post with PCB caution signs on the non-Work Area side. Provide all non-Work Area stairs and corridors accessible to the PCB Work Area with warning tapes at the base of stairs and beginning of corridors. Warning tapes shall be in addition to caution signs.
- B. Access to areas of work shall be regulated to prevent unauthorized visitors.
- C. All ground surfaces exterior to the work area shall have a layer of 6 mil fire retardant polyethylene sheeting, attached to the building face and laid down on the surface below the exterior abatement work area, at least 10 feet wide or to the furthest point of gravity fall for dislodged debris by methods used, whichever is further. All operable windows within the work area and 25 ft. from all sides of the work area shall be closed. In the vicinity of the removals, isolate all HVAC equipment intakes by temporarily shutting down units during removals and installing plastic sheeting over the opening.

3.2.3 REMOVAL OF PCB MATERIALS:

- A. PCB-containing materials shall be removed in accordance with the Contract Documents and the approved PCB Work Plan.
- B. Non-PCB items such as masonry, and all other building construction and components from which PCB materials are removed shall be decontaminated by physical or chemical means (such as stripper) such that no *visible* residue remains. The removal of the PCB materials may require the use of scrapers, solvents, mastic removal chemicals, or other methods/procedures

Lord Associates, Inc. Page 5 of 9

- to ensure complete removal. Post abatement verification sampling will be done on these surfaces in accordance with section 3.2.4 of this Plan.
- C. Mechanical cutting or grinding of PCB materials is not permitted, unless the equipment has factory- equipped HEPA filtered exhaust.
- D. Remove accessible caulking that could be disturbed before cutting building components, such as window frames.
- E. All removed PCB material shall be placed into 6 mil plastic disposal bags or other suitable container upon detachment from the substrate. Large components with PCB material or PCB residue shall be wrapped in one layer of 6 mil polyethylene sheeting. Sharp components likely to tear disposal bags shall be placed in fiber drums or boxes and then wrapped with sheeting.
- F. Power or pressure washers are not permitted for PCB removal or clean-up procedures.
- G. All construction and demolition debris determined by the Environmental Consultant to be contaminated with PCB shall be handled and disposed of as PCB waste. If the 40 CFR 761 Subpart S double wash-rinse technique is used to decontaminate non-porous surfaces such as movable equipment, tools, and sampling equipment, sampling is not required and the material may be considered non-PCB.
- H. All PCB waste must be located at or near the point of generation, under the control of the Project Supervisor. Up to 55 gallons may be stored at the point of generation for an indefinite period, but any more than 55 gallons must be moved within 3 days to a Container Storage Area (CSA) or off-site. Waste may be stored at the CSA for 90 days, during which labeling, inspections, and other requirements must be met as described in 40 CFR 761.
- I. Closure of the CSA. If an EPA ID number and CSA were created specifically for the PCB removal work, the Contractor must also close out the CSA and the Consultant shall notify the NHDES/EPA that the hazardous waste activity has concluded, and that the storage area is to be closed.
- J. Personal protective equipment, including respirators, shall be utilized and worn during all removal operations until the Work Area is cleared by the Abatement Project Monitor (APM).
- K. Following completion of gross abatement and after all accumulations of PCB waste materials have been containerized, the decontamination procedures in Section 3.2.4 shall be followed.

3.2.4 EQUIPMENT AND AREA DECONTAMINATION:

A. When removal of PCB materials is completed, the decontamination process shall consist of vacuuming (with a HEPA filter), wet wiping/mopping and a repeated vacuuming (with a HEPA

Lord Associates, Inc. Page 6 of 9

- filter) of the entire work area. All surfaces in and around the work area must be free of dust generated during the work.
- B. Decontaminate all tools and equipment before removal from the work area in accordance with 40 CFR 761 Subpart S double wash-rinse technique.
- C. Based on visual observation, if dust or debris has migrated through the dust barriers to areas of the building other than the immediate work area, those areas shall be incorporated into the work area and thoroughly decontaminated to ensure all visible dust generated by the activity is eliminated.
- D. Dust barriers and other protective sheeting shall be placed in disposable construction bags and disposed of as PCB Remediation Waste.
- E. Visually inspect the area for any remaining dust or debris. Vacuum (with HEPA filter) and wet wipe until space is clean. Dispose of vacuum contents as PCB Remediation Waste.
- F. Upon completion of decontamination and removing temporary dust barriers, a final inspection shall be performed by the Contractor and APM.

3.3 Schedule:

Planning work will commence once EPA approval is obtained. A definitive work schedule will be prepared once the project has been successfully bid and awarded.

3.4 Quality Control and Assurance Plan:

3.4.1 Post Abatement Verification Sampling:

Following the removal of all PCB Bulk Material, a visual inspection of the work site area will be performed to verify the removal of all such visible (caulk/paint) material and to collect confirmatory samples from the adjacent material substrate for laboratory analyses. A minimum of three representative samples will be collected from the window and door openings in Building Addition #3.

Samples of the adjacent material substrate will be collected using manual chiseling and/or drilling, placed in zip-lock bags and delivered to the lab under chain-of-custody protocol. See **Appendix C** for EPA Standard Operating Procedures for Sampling Porous Surfaces for PCBs.

3.4.2 Laboratory Methods & Associated QA/QC

The subcontracted laboratory will be National Environmental Laboratory Accreditation Program (NELAP) certified and follow EPA Method 3540C for soxhlet extractions and Method 8082 for gas chromatography analysis. A blind duplicate sample will be submitted at the 10% level. Intra-laboratory QA/QC data

Lord Associates, Inc.

Page 7 of 9

including matrix spike recovery and duplicates will be reported. Any exceptions will be discussed in a lab report narrative.

All reported data will be validated for Precision, Accuracy, Representativeness, Completeness, Comparativeness, and Sensitivity (PARCCS). In lieu of established QA/QC parameters for caulk, brick, and mortar, the following accuracy and precision parameters for soil will be used to evaluate these data:

Table 3 Laboratory Quality Control Parameters

Analyte	Matrix	Analytical Method	Reporting Limit	Precision (RPD%)	Accuracy (% LSC rec)
Aroclor 1016	Soil	8082	500 µg/Kg	50	38-158
Aroclor 1221	Soil	8082	500 µg/Kg	50	38-158
Aroclor 1232	Soil	8082	500 µg/Kg	50	38-158
Aroclor 1242	Soil	8082	500 µg/Kg	50	38-158
Aroclor 1248	Soil	8082	500 µg/Kg	50	38-158
Aroclor 1254	Soil	8082	500 µg/Kg	50	38-158
Aroclor 1260	Soil	8082	500 µg/Kg	50	38-158

3.5 Contingency Plan:

In the event that concentrations of PCB Bulk Product Waste > 50 ppm is identified in remaining building materials following the post-cleanup quality control sampling, that material will also be removed in accordance with the objectives of the Plan.

In the event that concentrations of PCB Remediation Waste >1 ppm is identified in remaining building materials following cleanup, that material will also be removed.

4.0 Remedial Waste Management:

All PCB material removed for off-site disposal will be managed in accordance with section 3.2.3 of this plan until transported to the approved disposal facility. While on-site, the waste containers shall be labeled with PCB warning labels as specified at 40 CFR 761. The waste containers will be transported under a Uniform Hazardous Waste Manifest by a NHDES licensed transporter, and marked "Polychlorinated biphenyl, solid mixture UN 3432", in accordance with DOT 49 CFR Parts 171 and 172.

- All PCB Bulk Product Waste (e.g., windows, doors, and frame trim) will be disposed of at a RCRA Subtitle C facility approved to accept TSCA waste.
- All building materials or soil identified as PCB Remediation Waste will be disposed of at a RCRA Subtitle C or D facility approved to accept such waste.

Lord Associates, Inc. Page 8 of 9

 All Decontamination Wastes will be disposed of in the roll-off containers used for the disposal of Bulk Product Waste.


5.0 Maintenance and Monitoring:


No continuing maintenance or monitoring will be required.

6.0 Notifications and Public Involvement:

Copies of this abatement plan are being provided to The New Hampshire Department of Environmental Services and the Concord Department of Public Health concurrently with the submission to EPA. As the school will be vacant during the abatement and demolition process, public notification will be limited to these entities. Notification of the work schedule will be made at least one week in advance.

Lord Associates, Inc. Page 9 of 9





Lord Associates, Inc.

PHOTOGRAPHIC RECORD






Photo View of Front of Building and Addition#1



Photo View of East Side Addition #3 #3:



Photo View of East Side Addition #3, location of sample #13 #2:



Photo Rear of Addition #3 #4:

Lord Associates, Inc.

PHOTOGRAPHIC RECORD






Photo View of Rear Addition #3 #5:



Photo View of Addition #2, looking south #7:



Photo View of Rear Addition #3, west side, location of sample #4 #6:



Photo View of Addition #4 #8:

http://www.emsl.com

3 Cooper St. Westmont, NJ 08108 Phone: (856) 858-4800

Fax: (856) 858-4571

EMSL.

Attn:

Allan Mercier RPF Associates 320 First NH Turnpike Northwood, NH 03261

Phone: (603) 942-5432 Fax: (603) 942-5300 3/15/2010

The following analytical report covers the analysis performed on samples submitted to EMSL Analytical, Inc. on 3/1/2010. The results are tabulated on the attached data pages for the following client designated project:

10.3610 - Conant

The reference number for these samples is EMSL Order #011000751. Please use this reference when calling about these samples. If you have any questions, please do not hesitate to contact me at (856) 858-4800.

Reviewed and Approved By:

Julie Smith - Laboratory Director or other approved signatory

signatory



The test results contained within this report meet the requirements of NELAC and/or the specific certification program that is applicable, unless otherwise noted.

NJ-NELAP Accredited: 04653

The samples associated with this report were received in good condition unless otherwise noted. This report relates only to those items tested as received by the laboratory. The QC data associated with the sample results meet the recovery and precision requirements established by the NELAP, unless specifically indicated. All results for soil samples are reported on a dry weight basis, unless otherwise noted. This report may not be reproduced except in full and without written approval by EMSL Analytical, Inc.

RPF Associates, Inc. ENVIRONMENTAL TESTING & CONSULTING

TABLE 3

SAU 8-Conant School HMFH

For Polychlorinated Biphenyls (PCBs) Preliminary Analytical Results

Environmental Site Assessments Asbestos & Hazardous Materials Industrial Hyglene Consulting Air Quality Testing & Analysis Mold and Moisture Surveys Infrared Thermal Imaging

OS Sample	Sample Locations	PCB-1016	DCB.1331	DC-1233	2 1221 DCD 1222 BCB 1242 BCB	19.00 and a	The same	4		
- 1		70.0	(DDM)	(mnm)	(mm)	PCB-1248	PCB-1254	PCB-1260	PCB-1262	PCB-126
022310-B01	Caulking, southwest entry door in hallway, interior	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99	(mdd) <0.99	(mdd) <0.99	(mdd) <0.99
022310-B02	Caulking, south entry door in room 2	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99
022310 -B 03	Caulking, southwest entry door in hallway, exterior	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99	<0.99
022310-B04	Caulking, old section bathroom sinks	<0.82	<0.82	<0.82	<0.82	<0.82	2.0	<0.82	<0.82	<0.82
022310-B05	Caulking, tan, hallway across from room 16 at building seam	<0.53	<0.53	<0.53	<0.53	<0.53	2.0	<0.53	<0.53	<0.53
022310-B06	Paint Chip, white, Boiler Room, Wall	>0.96	>0.96	>0.96	>0.96	>0.96	>0.96	>0.96	<0.96	<0.96
e22310-B07 ∓	Paint Chip, Grey, Boiler Room, Stairs	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
averhill Road • Suite 354 • Amesbury, MA 01 P. 978.388.9114 • F.978.388.9113	S H H	rts per million r EPA Method ' indicate dupli	(ppm) 8082 icate analyses f	for QA/QC.						
913									6	

320 First NH Turnpike • Northwood, P. 603.942.5432 • F. 603.942.5



EMSL – MA 7 Constitution Way, Suite 107 Woburn, MA 01801 (781) 933-8411 (781) 933-8412 Fax

EMSL - CT 4 Fairfield Blvd. Wallingford, CT 06492 (203) 284-5948 (203) 284-5978 Fax EMSL - NY 307 West 38th Street New York, NY 10018 (866) 448-3675 (212) 290-0058 Fax

1111111111

EMSL – NJ 107 Haddon Avenue Westmont, NJ 08108 (800) 220-3675 (856) 858-4960 Fax

Your Name:	ALLAN D.	MERCIER	Project M	anager: AM	
Company:	RPF Associates, Inc.			7711	
Street:	320 First NH Tumpike				
City/State/Zip	Northwood, NH 0326				
Phone:	603-942-5432	Fax; 60	03-942-5300	Email: ellan @ail	of cal
Project Name	HMEH		Pr	oject #: 10,3610	pr. com
Project Locat				Project Sta	ite (US): AD /4
	COIGHNI	TURNARO	IND THAT	1,10,100,000	19/4
☐ 3 Hours [☐ 6 Hours ☐ 12 Hours	TURNAROL 24 Hours		□ 4 Days □ 5 Days	A 6-10 Days
	MI	SAMPLE			1/1
□ Air	Soll Soll	☐ Wipe ☐ Micro-Vac	☐ Drinking Wi	ater	Other
TEM BULK Drop Mount (Quality Chatfield SOP-1986 TEM MICROVAC ASTM D 5755-95 (CTEM WIPE ASTM D-6480-99 Qualitative TEM WATER EPA 100.1 EPA 100.2 NYS 198.2 Other	Part 763 Subpart E e 2 Count urce Board (CARB) 435 etric) NYS 198.1 400 Points) 1,000 Points) Point Count thative ntitative ntitative viethod fibers/gram 0-R097-028 (dust generation) ative) 3-02 atric) NY 198.4	Soli, SW846-7420 Air, NIOSH 7082	ption ASTM non ASTM or AOAC 5.009 (974.02) -7420 1311/7420 pmic Absorption -7421 239.2 upled Plasma ASTM non ASTM IALYSIS dition fication ficatio	Mold & Fungi – Culti Mold & Fungi – Culti Bacterial Count & Gi Bacterial Count & Idi (3 most prominent ty Cither	C) Cell or Plate count & id Gram Stain dentification al Coliforms cal Streptococcus poridium bles ct Examination cure follow up to cition if necessary) ure (Count & ID) ren (Count only) ram Stain entification pes)
Client Sample # (\$	12221012 10 10	- 06	12310805	TOTAL SAMPLE #	5
telinquished:	Illan Men		Date:	/26/60 Time:	UPS
Received:	60		Date:	2/// Time:	0.)
elinquished:			Date:	Time:	
eceived:			Date:	Time:	



EMSL – MA 7 Constitution Way, Suite 107 Woburn, MA 01801 (781) 933-8411 (781) 933-8412 Fax

EMSL – CT 4 Fairfield Blvd. Wallingford, CT 06492 (203) 284-5948 (203) 284-5978 Fax

EMSL - NY 307 West 38* Street New York, NY 10018 (866) 448-3675 (212) 290-0058 Fax EMSL – NJ 107 Haddon Avenue Westmont, NJ 08108 (800) 220-3675 (856) 858-4960 Fax

4	SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	VOLUME Air (L)	Area (inches sq.)
	022310801	CAULKING	6.69	
2)	Boa		5.1 Dea	
多	B03		6.0	
4	V B04		2.4	
5	V B05	V	2.0	
6	BOL	PAINT BR W	2.0	
2	807	PANT BR W PANT GRY B.R. STAIRS	8.1	
	*	-		
-				
		-		
	*			
	4	V		
1				
				-
SFP - S	Stop at First Positive per Homo	ogeneous Group		
Relinquish	ned:	Date:	Time:	
Received:	-60-	Date: 3/1/10		
Relinquish	ed:	Date:	Time:	
Received:		Date:	Time:	



3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Allan Mercier RPF Associates 320 First NH Turnpike Northwood, NH 03261

Customer ID:

RPFA50

Customer PO: Received:

03/01/10 8:19 AM

EMSL Order:

011000751

Fax: (603) 942-5300

Phone: (603) 942-5432

Project: 10.3610 - Conant

Client Sample Description	022310B01 Caulking	Collected	2/2:	3/2010	Lab ID:	0001	
Method	Parameter	Concentration	Reporting Limit				
3540C/8082	Arador-1016			0,1110		lysis Date	
3540C/8082	Arocior-1221	<0.99	0.99	0 0		3/11/201	
3540C/8082	Arodor-1232	<0.99	0.99			3/11/201	
3540C/8082	Aroclor-1242	<0.99	0.99	0 0		3/11/2010	
3540C/8082	Aroclor-1248	<0.99 <0.99	0.99	5 5		3/11/2010	
3540C/8082	Aroclor-1254	<0.99	0.99	• •		3/11/2010	
3540C/8082	Aroclor-1260	<0.99	0.99			3/11/2010	
3540C/8082	Aroclor-1262	<0.99	0.99	mg/Kg		3/11/2010	
3540C/8082	Arodor-1268	<0.99	0.99	0 0		3/11/2010	
ant Cample Description		~0.55	0.99	mg/Kg		3/11/2010	ehemande
ent Sample Description	022310B02 Caulking	Collected:	2/23	2010	Lab ID:	0002	
	Osterially,						
Method	Parameter		Reporting Limit				
540C/8082	Aroclor-1016	Concentration		Units	Analy	vsis Date	Analyst
540C/8082	Aroclor-1221	<0.99	0.99	mg/Kg		/11/2010	
540C/8082	Aroclor-1232	<0.99	0.99	mg/Kg	3	/11/2010	ehemande
540C/8082	Aroclor-1242	<0.99	0.99	mg/Kg	3	/11/2010	ehernande
540C/8082	Arodor-1248	<0.99	0.99	mg/Kg		/11/2010	ehernande
540C/8082	Aroclor-1254	<0.99	0.99	mg/Kg		/11/2010	ehernande
540C/8082	Aroclor-1260	<0.99	0.99	mg/Kg	3/	11/2010	ehemande
540C/8082	Arodor-1262	 <0.99		mg/Kg	3/	11/2010	ehernande
40C/8082	Arodor-1268	<0.99		mg/Kg	3/	11/2010	ehernande:
70		<0.99	0.99	mg/Kg	3/	11/2010	ehernandez
lient Sample Description	022310B03 Caulking	Collected:	2/23/2	010	Lab ID:	0003	
ethod	Parameter		Reporting				
40C/8082	Aroclor-1016	Concentration		Units	Analys	is Date	Analyst
40C/8082	Arocior-1221	<0.99		mg/Kg		11/2010	ehemandez
40C/8082	Aroclor-1232	<0.99		mg/Kg	3/	11/2010	ehernandez
4DC/8082	Aroclor-1242	<0.99		mg/Kg	3/1	11/2010	ehemandez
40C/8082	Aroclor-1248	<0.99		mg/Kg		1/2010	ehemandez
10C/8082	Aroclor-1254	<0.99	0.99			1/2010	ehemandez
IOC/8082	Aroclor-1260	<0.99	0.99 1			1/2010	ehernandez
		<0.99	0.99		3/1	1/2010	ehemandez
3/8082	Arocior-1262	<0.99	0.99 r			1/2010	



3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmlth@emsl.com



Attn: Alian Mercier **RPF** Associates 320 First NH Turnpike Northwood, NH 03261

Customer ID:

RPFA50

Customer PO:

Received:

03/01/10 8:19 AM

EMSL Order:

011000751

Fax: (603) 942-5300

Phone: (603) 942-5432

Project: 10.3610 - Conant

Parameter Aroclor-1268 022310B04 Caulking Parameter Aroclor-1016 Aroclor-1221 Aroclor-1232	Concentration <0.99 Collected: Concentration <0.82 <0.82	Reporting Limit 0.99 2/23/ Reporting Limit 0.82	Units mg/Kg 2010	Analysis Date 3/11/2010 Lab ID: 0004 Analysis Date	Analyst ehernandez
022310B04 Caulking Parameter Aroclor-1016 Aroclor-1221 Aroclor-1232	Collected: Concentration <0.82	2/23/ Reporting Limit	2010	Lab ID: 0004	ehemande:
Parameter Aroclor-1016 Aroclor-1221 Aroclor-1232	Concentration <0.82	Reporting Limit			
Parameter Aroclor-1016 Aroclor-1221 Aroclor-1232	<0.82	Limit	Units	Analysis Date	
Aroclor-1016 Aroclor-1221 Aroclor-1232	<0.82	Limit	Units	Analysis Date	
Aroclor-1016 Aroclor-1221 Aroclor-1232	<0.82	0.82			Analyst
Arodor-1221 Arodor-1232			mg/Kg	3/11/2010	ehernande:
Aroclor-1232		0.82	mg/Kg	3/11/2010	ehernande
	<0.82	0.82	mg/Kg	3/11/2010	ehernande:
Aroclor-1242	<0.82	0.82	mg/Kg	3/11/2010	ehernande:
Arocior-1248	<0.82	0.82		3/11/2010	ehernande
Aroclor-1254	0.95	0.82		3/11/2010	ehemande
Arocior-1260	<0.82	0.82	mg/Kg	3/11/2010	ehernande
Arocior-1262	<0.82	0.82	mg/Kg	3/11/2010	ehernande
Aroclor-1268	<0.82	0.82	mg/Kg	3/11/2010	ehemande
022310B05	Collected:	2/23/	2010	Lab 1D: 0005	
Caulking					
Danamatan	Concentration		Linite	Analysis Date	Analyst
				-	ehemande:
					ehemandez
					ehernandez
					ehernandez
					ehemandez
					ehernandez
	<0.53			3/11/2010	ehernandez
Aroclor-1262	<0.53			3/11/2010	ehernandez
Arocior-1268	<0.53		_	3/11/2010	ehemande
022310B06	Collected:	2/23/	2010	Lab ID: 0006	
Paint BR W					
Parameter		Reporting Limit	Units	Analysis Date	Analyst
	<0.96			•	ehernandez
					ehemandez
	Aroclor-1260 Aroclor-1262 Aroclor-1268 D22310B05 Caulking Parameter Aroclor-1016 Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248 Aroclor-1254 Aroclor-1260 Aroclor-1262 Aroclor-1268 22310B06	Aroclor-1260 <0.82 Aroclor-1268 <0.82 Aroclor-1268 <0.82 Caulking Parameter Concentration Aroclor-1016 <0.53 Aroclor-1221 <0.53 Aroclor-1222 <0.53 Aroclor-1232 <0.53 Aroclor-1242 <0.53 Aroclor-1248 <0.53 Aroclor-1254 <0.53 Aroclor-1260 <0.53 Aroclor-1260 <0.53 Aroclor-1260 <0.53 Aroclor-1262 <0.53 Aroclor-1268 <0.53 Aroclor-1268 <0.53 Aroclor-1268 <0.53 Aroclor-1269 <0.53 Aroclor-1260 <0.53 Aroclor-1260 <0.53 Aroclor-1260 <0.53 Aroclor-1261 <0.53 Aroclor-1262 <0.53 Aroclor-1268 <0.53 Collected: Concentration Aroclor-1016 <0.96 Aroclor-1221 <0.96	Aroclor-1260	Aroclor-1260	Aroclor-1260



3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Allan Mercier RPF Associates 320 First NH Turnpike Northwood, NH 03261

Customer ID:

RPFA50

Customer PO:

Received:

03/01/10 8:19 AM

EMSL Order:

011000751

Fax: (603) 942-5300

Phone: (603) 942-5432

Project: 10.3610 - Conant

-		Analytical Results				
Client Sample Description	022310B06 Paint BR W	Collected:	2/23	3/2010	Lab ID: 0006	
Method	Parameter	Concentration	Reporting Limit	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1232	<0.96	0.96		3/11/2010	ehemande
3540C/8082	Aroclor-1242	<0.96	0.96		3/11/2010	ehemande
3540C/8082	Arodor-1248	<0.96	0.96		3/11/2010	ehemande
3540C/8082	Aroclor-1254	<0.96	0.96		3/11/2010	ehemande
3540C/8082	Arcclor-1260	<0.96	0.96	mg/Kg	3/11/2010	ehemande
3540C/8082	Aroclor-1262	<0.96	0.96	mg/Kg	3/11/2010	ehemande
3540C/8082	Aroclor-1268	<0.96	0.96	mg/Kg	3/11/2010	ehernande
Client Sample Description	022310B07	Collected:	2/23/	2010	Lab ID: 0007	
	Paint Grey B.R. Stairs	man so on this these	2,20	2010	Lab ID. 0007	
thod	Parameter	Concentration	Reporting Limit	Units	Analysis Date	Analyst
1540C/8082	Aroclor-1016	<1.0	1.0	mg/Kg	3/11/2010	ehemande
540C/8082	Aroclor-1221	<1.0	1.0	mg/Kg	3/11/2010	ehernande
540C/8082	Aroclor-1232	· <1.0	1.0	mg/Kg	3/11/2010	ehernande
540C/8082	Arocior-1242	<1.0	1.0	mg/Kg	3/11/2010	ehernande
540C/8082	Aroclor-1248	<1.0	1.0	mg/Kg	3/11/2010	ehemande:
540C/8082	Aroclor-1254	<1.0	1.0	mg/Kg	3/11/2010	ehemande:
540C/8082	Arodor-1260	<1.0	1.0	mg/Kg	3/11/2010	ehemandez
540C/8082	Aroclor-1262	<1.0	1.0	mg/Kg	3/11/2010	ehemandez
540C/8082	Aroclor-1268	<1.0	1.0	mg/Kg	3/11/2010	ehemandez

http://www.emsl.com

3 Cooper St. Westmont, NJ 08108 Phone: (856) 858-4800

Fax: (856) 858-4571

Attn: **Ammar Dieb**

Universal Environmental Consultants

12 Brewster Road Framingham, MA 01702

Phone: (508) 628-5486 Fax: (508) 628-5488 8/25/2011

The following analytical report covers the analysis performed on samples submitted to EMSL Analytical, Inc. on 8/11/2011. The results are tabulated on the attached data pages for the following client designated project:

Concord, NH Conant Elem. School

The reference number for these samples is EMSL Order #011104037. Please use this reference when calling about these samples. If you have any questions, please do not hesitate to contact me at (856) 858-4800.

Reviewed and Approved By:

Julie Smith - Laboratory Director other approved

signatory



The test results contained within this report meet the requirements of NELAC and/or the specific certification program that is applicable, unless otherwise noted. NELAP Certifications: NJ 04653, NY 10896, PA 68-00367

The samples associated with this report were received in good condition unless otherwise noted. This report relates only to those items tested as received by the laboratory. The QC data associated with the sample results meet the recovery and precision requirements established by the NELAP, unless specifically indicated. All results for soil samples are reported on a dry weight basis, unless otherwise noted. This report may not be reproduced except in full and without written approval by EMSL Analytical, Inc.



3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Ammar Dieb

Fax: (508) 628-5488

Universal Environmental Consultants

12 Brewster Road

Framingham, MA 01702

Phone: (508) 628-5486

Project: Concord, NH Conant Elem. School

Customer ID:

UEC63

Customer PO:

Received:

08/11/11 3:00 PM

EMSL Order:

011104037

Client Sample Description	1 white paint (wp) original and main out wood	Collected:	8/10/2011	Lab ID: 0001	
	white paint (wp) orig bldg main ent, wood column				
Method	Parameter	Result	Reporting Limit Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.50 mg/Kg	8/18/2011	ehernande:
3540C/8082	Aroclor-1221	ND	0.50 mg/Kg	8/18/2011	ehernande:
3540C/8082	Aroclor-1232	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1242	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1248	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1254	5.3	0.50 mg/Kg	8/18/2011	ehernande
Aroclor 1254 was detected in the slightly above the reporting limit, result may be biased high. Samp during extraction.	therefore the		- 0		
3540C/8082	Aroclor-1260	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1262	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1268	ND	0.50 mg/Kg	8/18/2011	ehernande
Client Sample Description	2	Collected:	8/10/2011	Lab ID: 0002	
	wp additon #2, wood window column				
Method	Parameter	Result	Reporting Limit Units	Analysis Date	Analyst
540C/8082	Aroclor-1016	ND	0.49 mg/Kg	8/23/2011	ehernandez
540C/8082	Aroclor-1221	ND	0.49 mg/Kg	8/23/2011	ehernande
540C/8082	Aroclor-1232	ND	0.49 mg/Kg	8/23/2011	ehernandez
540C/8082	Aroclor-1242	ND	0.49 mg/Kg	8/23/2011	ehernande
540C/8082	Aroclor-1248	ND	0.49 mg/Kg	8/23/2011	ehernandez
540C/8082	Aroclor-1254	ND	0.49 mg/Kg	8/23/2011	ehernandez
540C/8082	Aroclor-1260	ND	0.49 mg/Kg	8/23/2011	ehernandez
540C/8082	Aroclor-1262	ND	0.49 mg/Kg	8/23/2011	ehernandez
540C/8082	Aroclor-1268	ND	0.49 mg/Kg	8/23/2011	ehernandez
Client Sample Description	3	Collected:	8/10/2011	Lab ID: 0003	
	wp original bldg, side entrance				
# d	_		Reporting		
fethod	Parameter	Result	Limit Units	Analysis Date	Analyst
540C/8082	Aroclor-1016	ND	0.50 mg/Kg	8/18/2011	ehernandez
540C/8082	Aroclor-1221	ND	0.50 mg/Kg	8/18/2011	ehernandez
540C/8082	Aroclor-1232	ND	0.50 mg/Kg	8/18/2011	ehernandez
540C/8082	Aroclor-1242	ND	0.50 mg/Kg	8/18/2011	ehernandez
o - m Consult / DDI / NEI A C					
memompiw/RDL/NELAC-7.2	21.0 Printed: 8/25/2011 12:50:46 PM				Page 2 of 7



3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Page 3 of 7

Attn: Ammar Dieb

Fax: (508) 628-5488

Universal Environmental Consultants

12 Brewster Road

Framingham, MA 01702

Phone: (508) 628-5486

Project: Concord, NH Conant Elem. School

ChemSmplw/RDL/NELAC-7.21.0 Printed: 8/25/2011 12:50:46 PM

Customer ID:

UEC63

Customer PO:

Received:

08/11/11 3:00 PM

EMSL Order:

011104037

Client Sample Description	3	Collected:	8/10	/2011	Lab ID: 0003	
	wp original bldg, side entrance					
			Reporting			
Method	Parameter	Result	Limit	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1248	ND	0.50	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1254	ND	0.50	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1260	ND	0.50	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1262	ND	0.50	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1268	ND	0.50	mg/Kg	8/18/2011	ehernandez
Client Sample Description	4	Collected:	8/10/	/2011	Lab ID: 0004	
	wp additional #3, old wood door fr.					
	_		Reporting			
Method	Parameter	Result	Limit	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	12	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1221	ND	12		8/18/2011	ehernandez
3540C/8082	Aroclor-1232	ND	12	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1242	ND		mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1248	ND		mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1254	96	12	mg/Kg	8/18/2011	ehernandez
Aroclor 1254 was detected in the slightly above the reporting limit, result may be biased high. Samp during extraction.	therefore the					
3540C/8082	Aroclor-1260	ND	12	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1262	ND	12	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1268	ND	12	mg/Kg	8/18/2011	ehernandez
Client Sample Description	5	Collected:	8/10/	2011	Lab ID: 0005	
	wp clg @ c'rm #5					
Method	Parameter	Result	Reporting Limit	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.49	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1221	ND	0.49	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1232	ND	0.49	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1242	ND	0.49	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1248	ND	0.49	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1254	1.1		mg/Kg	8/18/2011	ehernandez
Aroclor 1254 was detected in the slightly above the reporting limit, result may be biased high. Sampl during extraction.	therefore the			3.43		



3. Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Ammar Dieb

Universal Environmental Consultants

12 Brewster Road Framingham, MA 01702

Customer ID: Customer PO: UEC63

Received:

08/11/11 3:00 PM

EMSL Order:

011104037

Fax: (508) 628-5488

Phone: (508) 628-5486

Project: Concord, NH Conant Elem. School

Client Sample Description	5	Collected:	8/10/2011	Lab ID: 0005	
	wp clg @ c'rm #5				
Mathad	Paramatan		eporting		
Method	Parameter	Result	Limit Units	Analysis Date	Analyst
3540C/8082	Aroclor-1260	ND	0.49 mg/Kg		ehernande
3540C/8082	Aroclor-1262	ND	0.49 mg/Kg		ehernande
3540C/8082	Aroclor-1268	ND	0,49 mg/Kg	8/18/2011	ehernande
Client Sample Description	6	Collected:	8/10/2011	Lab ID: 0006	
	wp on radiator shield, c'rm #7				
		R	eporting		
Method	Parameter	Result	Limit Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.48 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1221	ND.	0.48 mg/Kg		ehernande
3540C/8082	Aroclor-1232	ND	0.48 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1242	ND	0.48 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1248	ND	0.48 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1254	ND	0.48 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1260	ND	0.48 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1262	ND	0.48 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1268	ND	0.48 mg/Kg	8/18/2011	ehernande
Client Sample Description	7	Collected:	8/10/2011	Lab ID: 0007	
	horiz. Win frame caulk orig bldg rear				
		Re	porting		
Method	Parameter	Result	Limit Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1221	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1232	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1242	ND	0.50 mg/Kg	8/18/2011	ehernande
540C/8082	Aroclor-1248	ND	0.50 mg/Kg	8/18/2011	ehernande
540C/8082	Aroclor-1254	ND	0.50 mg/Kg	8/18/2011	ehernande
540C/8082	Aroclor-1260	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1262	ND	0.50 mg/Kg	8/18/2011	ehernande
3540C/8082	Aroclor-1268	ND	0.50 ma/Ka		



Fax: (508) 628-5488

EMSL Analytical, Inc.

3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Ammar Dieb

Universal Environmental Consultants

12 Brewster Road

Framingham, MA 01702

Phone: (508) 628-5486

Project: Concord, NH Conant Elem. School

Customer ID:

UEC63

Customer PO:

Received:

08/11/11 3:00 PM

EMSL Order:

011104037

	old door fr caulk orig bldg rear					
	· ·					
14 d	n		Reporting		4.1.5.	
Method	Parameter	Result	_	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND		ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1221	ND		mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1232	ND		ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1242	ND		mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1248	ND		ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1254	ND		ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1260	ND		ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1262	ND	0.50 r	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1268	ND	0.50 r	ng/Kg	8/18/2011	ehernandez
Client Sample Description	9	Collected:	8/10/20	011	Lab ID: 0009	
	window vert fr caulk orig bldg rear					
			Reporting			
Method	Parameter	Result	Limit _l	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.49 r	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1221	ND	0.49 r	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1232	ND	0.49 r	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1242	ND	0.49 r	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1248	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1254	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1260	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1262	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1268	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
Client Sample Description	10	Collected:	8/10/20)11	Lab ID: 0010	
	window fr caulk orig bldg side entrance					
			Reporting			
Method	Parameter	Result	Limit _U	Inits	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1221	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1232	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1242	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1248	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1254	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1260	ND	0.49 n	ng/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1262	ND	0.49 n		8/18/2011	ehernandez



3. Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Ammar Dieb

Universal Environmental Consultants

12 Brewster Road Framingham, MA 01702

Customer ID:

UEC63

Customer PO: Received:

08/11/11 3:00 PM

EMSL Order:

011104037

Fax: (508) 628-5488

Phone: (508) 628-5486

Project: Concord, NH Conant Elem. School

Client Sample Description	10 window fr caulk orig bldg side entrance	Collected:	8/10	/2011	Lab ID: 0010	
			Reporting			
Method	Parameter	Result	Limit	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1268	ND	0.49	mg/Kg	8/18/2011	ehernandez
Client Sample Description	11	Collected:	8/10	/2011	Lab ID: 0011	
	Top Layer caulk bet wood column and brick					
Made at	Description	D 44	Reporting Limit	Trade-	Analysis Data	Anabias
Method	Parameter	Result		Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.50	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1221	ND	0.50		8/17/2011	ehernandez
3540C/8082	Aroclor-1232	ND	0.50	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1242	ND	0.50		8/17/2011	ehernandez
3540C/8082	Aroclor-1248	ND	0.50	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1254	ND	0.50		8/17/2011	ehernandez
3540C/8082	Aroclor-1260	ND	0.50	mg/Kg	. 8/17/2011	ehernandez
3540C/8082	Aroclor-1262	ND	0.50	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1268	ND	0.50	mg/Kg	8/17/2011	ehernandez
Client Sample Description	12	Collected:	8/10/	2011	Lab ID: 0012	
	old caulk bet wood column & brick main ent orig					
			Reporting			
Method	Parameter	Result	Limit	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.49	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1221	ND	0.49	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1232	ND	0.49	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1242	ND	0.49	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1248	ND	0.49	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1254	ND	0.49	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1260	ND	0.49	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1262	ND	0.49	mg/Kg	8/17/2011	ehernandez
3540C/8082	Aroclor-1268	ND	0.49	mg/Kg	8/17/2011	ehernandez
Client Sample Description	13	Collected:	8/10/	2011	Lab ID: 0013	
	window fr caulk addition #3					
Method	Parameter	Result	Reporting Limit	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	37	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1221	ND		mg/Kg	8/18/2011	ehernandez
ChemSmplw/RDL/NELAC-7.	21.0 Printed: 8/25/2011 12:50:46 PM			- -		Page 6 of 7



3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Ammar Dieb

Universal Environmental Consultants

12 Brewster Road

Framingham, MA 01702

Customer ID:

UEC63

Customer PO:

Received:

08/11/11 3:00 PM

EMSL Order:

011104037

Fax: (508) 628-5488

Phone: (508) 628-5486

Project: Concord, NH Conant Elem. School

Analytical Results

Client Sample Description	13 window fr caulk addition #3	Collected:	8/10/2	011	Lab ID: 0013	
Method	Parameter	R Result	eporting Limit	Units	Analysis Date	Analyst
3540C/8082	Aroclor-1232	ND	37	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1242	ND	37	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1248	ND	37	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1254	220	37	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1260	ND	37	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1262	ND	37	mg/Kg	8/18/2011	ehernandez
3540C/8082	Aroclor-1268	ND	37	mg/Kg	8/18/2011	ehernandez

Definitions:

ND - indicates that the analyte was not detected at the reporting limit

Ollo4037 CHAIN OF CUSTODY

Universal Environmental Consultants
12 Brewster Road
Framingham, MA 01702
Tel: (508) 628-5486 - Fax: (508) 628-548
adieb@uec-env.com

samples #1 - #4 = exterior #5, #6 = interior #7 - #13 = exterior

Town/City: Cascoed Mill Building Name Count Elem School

Sample	Result	Description of Material	Sample Location
		white paint (wp)	Sample Location
2		is P	Addition # 2, wood window
<i>'</i> 3		wp	original bldg, side ENTIAN
4		wp	Addition # 3, old wood door
.5		wP	cha e c'rm 45
G		WP	
7		windows frame can	Ik orig blog reac
8		old door for caulk	orighedy reak
9		window fr cault	orighted rear
10		window freaulk	
		Toplager CAUIKON OF	d caulk between wood colum
		(main ENTIANCE)	and brich - orig bldg
12		old calk between is	
		M	DIN ENTRANCE orighlde
/3		window fre coult	addition #3
	<u>-</u>		

Reported By:	Date: 08/10/11	Due Date: 10 day
Received By:	Date: 8/11/11 3:00pm	

8/ Der Ammen NO Certil Needer De

UNIVERSAL ENVIRONMENTAL CONSULTANTS

http://www.emsl.com

3 Cooper St. Westmont, NJ 08108 Phone: (856) 858-4800 Fax: (856) 858-4571



Attn:

Ammar Dieb

Universal Environmental Consultants

12 Brewster Road

Framingham, MA 01702

Fax:

Phone: (508) 628-5486 (508) 628-5488 12/1/2011

The following analytical report covers the analysis performed on samples submitted to EMSL Analytical, Inc. on 11/23/2011. The results are tabulated on the attached data pages for the following client designated project:

Conant School Addition 3

The reference number for these samples is EMSL Order #011105932. Please use this reference when calling about these samples. If you have any questions, please do not hesitate to contact me at (856) 858-4800.

Reviewed and Approved By:

Julie Smith - Laboratory Director pr other approved



The test results contained within this report meet the requirements of NELAC and/or the specific certification program that is applicable, unless otherwise noted. NELAP Certifications: NJ 04653, NY 10896, PA 68-00367

The samples associated with this report were received in good condition unless otherwise noted. This report relates only to those items tested as received by the laboratory. The QC data associated with the sample results meet the recovery and precision requirements established by the NELAP, unless specifically indicated. All results for soil samples are reported on a dry weight basis, unless otherwise noted. This report may not be reproduced except in full and without written approval by EMSL Analytical, Inc.



3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Ammar Dieb

Universal Environmental Consultants

12 Brewster Road

Framingham, MA 01702

Customer ID:

UEC63

Customer PO:

Received:

11/23/11 12:00 PM

EMSL Order:

011105932

Fax: (508) 628-5488

Phone: (508) 628-5486

Project: Conant School Addition 3

Client Sample Description	1 North Window Frame	Collected:	11/22/2011	Lab ID: 0001	
			Reporting		
Method	Parameter	Result	Limit Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.49 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1221	ND	0.49 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1232	. ND	0.49 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1242	ND	0.49 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1248	ND	0.49 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1254	ND	0.49 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1260	ND	0.49 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1262	ND	0.49 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1268	ND	0.49 mg/Kg	11/28/2011	ehernandez
Client Sample Description	2 South Window Frame	Collected:	11/22/2011	Lab ID: 0002	
		1	Reporting		
Method	Parameter	Result	Limit Units	Analysis Date	Analyst
3540C/8082	Aroclor-1016	ND	0.50 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1221	ND	0.50 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1232	ND	0.50 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1242	ND	0.50 mg/Kg	11/28/2011	ehernandez
8540C/8082	Aroclor-1248	ND	0.50 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1254	ND	0.50 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1260	ND	0.50 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1262	ND	0.50 mg/Kg	11/28/2011	ehernandez
3540C/8082	Aroclor-1268	ND	0.50 mg/Kg	11/28/2011	ehernandez
Client Sample Description	3 Southwest Corner Door Frame	Collected:	11/22/2011	Lab ID: 0003	
		R	Reporting		
1ethod	Parameter	Result	Limit Units	Analysis Date	Analyst
540C/8082	Aroclor-1016	ND	0.49 mg/Kg	11/28/2011	ehernandez
540C/8082	Aroclor-1221	ND	0.49 mg/Kg	11/28/2011	ehernandez
540C/8082	Aroclor-1232	ND	0.49 mg/Kg	11/28/2011	ehernandez
540C/8082	Aroclor-1242	ND	0.49 mg/Kg	11/28/2011	ehernandez
540C/8082	Aroclor-1248	ND	0.49 mg/Kg	11/28/2011	ehernandez
540C/8082	Aroclor-1254	ND	0.49 mg/Kg	11/28/2011	ehernandez
540C/8082	Aroclor-1260	ND	0.49 mg/Kg	11/28/2011	ehernandez
540C/8082	Aroclor-1262	ND	0.49 mg/Kg	11/28/2011	ehernandez
	21.0 Printed: 12/1/2011 6:32:44 AM				Page 2 of 3



3 Cooper St., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4571 Email: jsmith@emsl.com



Attn: Ammar Dieb

Universal Environmental Consultants

12 Brewster Road

Framingham, MA 01702

Customer ID:

UEC63

Customer PO:

Received:

11/23/11 12:00 PM

EMSL Order:

011105932

Fax: (508) 628-5488

Phone: (508) 628-5486

Project: Conant School Addition 3

Analytical Results

Client Sample Description

Southwest Corner Door Frame

Collected:

11/22/2011

Lab ID: 0003

Method

Parameter

Result

Limit Units

Analysis Date

Analyst

3540C/8082

Aroclor-1268

ND 0.49 mg/Kg

Reporting

11/28/2011

ehernandez

Definitions:

ND - indicates that the analyte was not detected at the reporting limit



01110 5932 universal environmental consultants

12 Brewster Road Framingham, MA 01702 Phone: 508.628.5486 Fax: 508.628.5488

CHAIN OF CUSTODY

BUILDIN	IG/SITE NAME: Conant WORK AREA: Addition	school	TOWN / CITY	: Co.	ncur	I		
	WORK AREA: Addition	on 3	STATE	: _ 1	/ H	_		-

	T	7. 19. 18. 2. 18. 18. 18. 18. 18. 18. 18. 18. 18. 18	S	Copper.	Mata	V\$.3/28/21-	Property of the state	Spring to
Analysis Type	Turnaround Time (x) 6-8 Hr 12 Hr 24 Hr 48 Hr	72 hr		ic Projec		ο,	1.	
TEM / AHERA		lest	for	PCI	<i>S s</i>	1300	cu	
TEM / Level II TEM / Dust			day T				Λ	
TEM / Bulk			dey T	レトへ	a	re u-	d	
TEM / Water			U					
PLM Mold								
Other:		¥ v						
SOFT SECTION STATES	Full and the second of the sec					Sant-Section 2	7.20是最级外长	2000年 (15)
SAMPLE ID	MATERIAL DESCRIPTION	SAMPLE LOCA		START	STOP	TIME	L/MIN	VOLUME
	Brick	north window			ļ	ļ		
2	(1	South window Southwest corner	Franc					
3	Brick.	Southwest corner	door Frame					
) ·		·						
\								
<u>/</u>		DATE SHEET DESCRIPTION	ED DV:	RHA	्रा _न ः		DA C	TE/TIME:
SAMPLED BY:	Jason Berte 11-22-1 DBY: Jason Berte 11-82-1	DATE/TIME: RECEIV						
RELINQUISHE	DBY:	DATE/TIME: RECEIV	ED IN LAB BY:	N()V 2 2	7	J PA	TE/TIME: 3/11/2:0
	Jason Beatle 11-82-1			BY:_	<u>sa</u>	1700	$\frac{1}{2}$	3/11/4.0
				l	SIM		,	



UEC universal environmental consultants

12 Brewster Road Framingham, MA 01702 Phone: 508.628.5486 Fax: 508.628.5488

CHAIN OF CUSTODY

BUILDIN	NG / SITE			7 5	cheel		·	TOWN /	CIT	۲: <u>ر</u>	once	ird		
	WOR	(AREA:						S	TAT	E:	14			
						· · · · · · · · · · · · · · · · · · ·								
Analysis	24年 李明	Turna	round Tin	ne (x)	5 沙洲洲海绵的山	7.4), 18° (1907) (A. Basilia)				ect Notes	. 178.01 V P	· Prober Charge	\$10°40'S '61
Туре	6-8 Hr	12 Hr	24 Hr	48 Hr	72 hr						oce mores			
TEM / AHERA						1	est f	-		•				
TEM / Dust							5-de					_		
TEM / Bulk	1	·····					5- de	y T	Tur	~ ~	10000			
TEM / Water					 			V						j
Mold														
Other:		SPAYORUS SOLO												
SAMPLE ID	MA'	TERIAL D	ESCRIPTIC)N), #F1 200-73 (7.100 #9#	SAM	PLE LOCATIO	835 99(685) 63 N	igenteralitest		T STOP		L/MIN	VOLUME
1.	Paint	wl	"te		rom	Sce	iling						1	
	faint				roun	4 ce:1	ing			T				
	Pain T	. wh	ite				iling							
4	Soil	<u>-</u>	· ``				3 North	5; d e	1					
\$	soil				add:	ti'an 3	3 Nort	h si a	le					
6	501				addi:	tia 3	rorth	s,'de						
	,													
	.,,,,													
					· · · · · · · · · · · · · · · · · · ·	VIII (11 11 11 11 11 11 11 11 11 11 11 11 11	····			 				
			 				· · · · · · · · · · · · · · · · · · ·				 			
				-+							 			
											 			
		····	· · · · · · · · · · · · · · · · · · ·				······································	<u> </u>			 			
	۲ ۸۰		. 1							<u> </u>				
			e, Not i											
<u> </u>	er Amma 11/12 111	of proce	ed w/ Ana	lysis										
3	filis W	24AM -	174											
		······································					······································		回		<u> </u>			
		~							N	L U		5		
MPLED BY: ゴム	son B	evote	2-29)-12	DA	TE/TIME:	RECEIVED BY	<u>':</u>		FEB	2 9 20	12	DAT	E/TIME:
LINQUISHED I	507 B BY: agons	7 a. 4	 محريد	とい	DA	TE/TIME:	RECEIVED IN	LAB BY:	B.,	50	(037))	2947	FE/TIME:
		semo	<i>0 0</i>	·			<u> </u>	4	ورس				- - 3/1/	ng 4.30Am

http://www.emsl.com

200 Route 130 North Cinnaminson, NJ 08077 Phone: (856) 858-4800 Fax: (856) 858-4571

Attn: Ammar Dieb

Universal Environmental Consultants

12 Brewster Road Framingham, MA 01702

3/8/2012

Phone: (508) 628-5486 Fax: (508) 628-5488

The following analytical report covers the analysis performed on samples submitted to EMSL Analytical, Inc. on 3/1/2012. The results are tabulated on the attached data pages for the following client designated project:

Concord NH

The reference number for these samples is EMSL Order #011200971. Please use this reference when calling about these samples. If you have any questions, please do not hesitate to contact me at (856) 858-4800.

Reviewed and Approved By:

Julie Smith - Laboratory Director or other approved signatory



The test results contained within this report meet the requirements of NELAC and/or the specific certification program that is applicable, unless otherwise noted. NELAP Certifications: NJ 03036, NY 10896, PA 68-00367

The samples associated with this report were received in good condition unless otherwise noted. This report relates only to those items tested as received by the laboratory. The QC data associated with the sample results meet the recovery and precision requirements established by the NELAP, unless specifically indicated. All results for soil samples are reported on a dry weight basis, unless otherwise noted. This report may not be reproduced except in full and without written approval by EMSL Analytical, Inc.



200 Route 130 North, Cinnaminson, NJ 08077

Phone: (856) 858-4800

Fax: (856) 858-4571 Email: jsmith@emsl.com

Attn: Ammar Dieb

Universal Environmental Consultants

12 Brewster Road Framingham, MA 01702 Customer ID:

UEC63

Customer PO: Received:

03/01/12 9:30 AM

EMSL Order:

011200971

Fax: (508) 628-5488

Phone (508) 628-5486

Project: Concord NH

Analytical Results

Client Sample Description	1	Collected:	2/29/	2012	Lab ID:	0001	
	Room 5 ceiling paint white						
Method	Parameter	Result	Reporting Limit	Units	Ana	lysis Date	Analyst
3540C/8082A	Aroclor-1016	ND	0.88	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1221	ND	0.88	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1232	ND	0.88	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1242	ND	0.88	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1248	ND.	0.88	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1254	1.7	0.88	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1260	ND.	0.88	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1262	ND	0.88	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1268	ND	0.88	mg/Kg		3/5/2012	ehernandez
Client Sample Description	2	Collected:	2/29/2	2012	Lab ID:	0002	
	Room 4 ceiling paint white						
			Reporting				
Method	Parameter	Result	Limit	Units	Anai	ysis Date	Analyst
3540C/8082A	Aroclor-1016	ii ND	0.49	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1221	ND	0.49	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1232	ND	0.49	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1242	ND	0.49	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1248	ND	0.49	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1254	ND	0.49	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1260	ND	0.49	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1262	ND	0.49	mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1268	ND ND	0.49	mg/Kg	* ************************************	3/5/2012	ehernandez
Client Sample Description	3	Collected:	2/29/2	2012	Lab ID:	0003	
	Room 9 ceiling paint white						
	.		Reporting				
Aethod	Parameter	Result		Units	Anal	vsis Date	Analyst
540C/8082A	Aroclor-1016	ND		mg/Kg		3/5/2012	ehernandez
540C/8082A	Aroclor-1221	ND		mg/Kg		3/5/2012	ehernandez
540C/8082A	Aroclor-1232	ND		mg/Kg		3/5/2012	ehernandez
540C/8082A	Aroclor-1242	ND		mg/Kg		3/5/2012	ehernandez
540C/8082A	Aroclor-1248	ND		mg/Kg		3/5/2012	ehernandez
540C/8082A	Aroclor-1254	ND		mg/Kg		3/5/2012	ehernandez
540C/8082A	Aroclor-1260	ND		mg/Kg		3/5/2012	ehernandez
3540C/8082A	Aroclor-1262	ND	0.70	mg/Kg		3/5/2012	ehernandez



200 Route 130 North, Cinnaminson, NJ 08077

Phone: (856) 858-4800

Fax: (856) 858-4571 Email: jsmith@emsl.com

Attn: Ammar Dieb

Universal Environmental Consultants 12 Brewster Road

Framingham, MA 01702

Customer ID:

UEC63

Customer PO:

Received: EMSL Order: 03/01/12 9:30 AM 011200971

Fax: (508) 628-5488

Phone (508) 628-5486

Project: Concord NH

Analytical Results

Client Sample Description	3 Room 9 ceiling paint white	Collected	: 2/29	/2012	Lab ID:	0003	
<i>Method</i> 3540C/8082A	Parameter Aroclor-1268	Result ND	Reporting Limit 0.70	<i>Units</i> mg/Kg	And	llysis Date 3/5/2012	Analyst ehernandez
Client Sample Description	4 Addition 3 north side soil	Collected:	2/29	/2012	Lab ID:	0004	
Method	Parameter	Result	Reporting Limit	Units	Ano	lysis Date	Analyst
SM 2540G	Total Solids	nes <i>iii</i> 66	N/A	% :	A STATE OF THE STA	3/5/2012	ાvu
3540C/8082A	Aroclor-1016	ND	76	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1221	ND	76	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1232	ND	76	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1242	· ·	76	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1248	ND	76	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1254	ND	76	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1260	ND	76	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1262	ND.	76	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1268	ND	76	μg/Kg		3/2/2012	ehernandez
Client Sample Description	5 Addition 3 north side soil	Collected:	2/29/	2012	Lab ID:	0005	
Method	Parameter	Result	Reporting Limit	Units	4 ~	lysis Date	A see as I see at
SM 2540G	Total Solids	Kesuu 58	N/A	%	Anai	•	Analyst
3540C/8082A	Aroclor-1016	ND	. IN/A 85			3/5/2012	lvu
3540C/8082A	Aroclor-1221	ND ND	85	μg/Kg μg/Kg		3/2/2012	ehernandez ehernandez
3540C/8082A	Aroclor-1232	ND	85	μg/Kg μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1242	ND ND	.85	μg/Kg μg/Kg		3/2/2012	ehernandez
540C/8082A	Aroclor-1248	ND	85	μg/Kg		3/2/2012	ehernandez
540C/8082A	Aroclor-1254	ND:	85	μg/Kg		3/2/2012	ehernandez
540C/8082A	Aroclor-1260	ND	85	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1262	ND.	85	μg/Kg		3/2/2012	ehernandez
3540C/8082A	Aroclor-1268	ND	85	μg/Kg		3/2/2012	ehernandez



200 Route 130 North, Cinnaminson, NJ 08077

Phone: (856) 858-4800

Fax: (856) 858-4571

Email: jsmith@emsl.com

Attn: Ammar Dieb

Universal Environmental Consultants 12 Brewster Road

Framingham, MA 01702

Customer ID:

UEC63

Customer PO:

Received: EMSL Order: 03/01/12 9:30 AM 011200971

Fax: (508) 628-5488

Phone (508) 628-5486

Project: Concord NH

Analytical Results

Client Sample Description	6	Collected:	2/29/2	2012	Lab ID: 0006	
	Addition 3 north side soil					
		1	Reporting			
Method	Parameter	Result	Limit	Units	Analysis Date	Analyst
SM 2540G	Total Solids	73	N/A	%	3/5/2012	lvu
3540C/8082A	Aroclor-1016	ND	68	μg/Kg	3/2/2012	ehernandez
3540C/8082A	Aroclor-1221	ND	68	μg/Kg	3/2/2012	ehernandez
3540C/8082A	Aroclor-1232	ND	68	μg/Kg	3/2/2012	ehernandez
3540C/8082A	Aroclor 1242	ND	68	μg/Kg	3/2/2012	ehernandez
3540C/8082A	Aroclor-1248	ND	68	μg/Kg	3/2/2012	ehernandez
3540C/8082A	Aroclor-1254	ND	68	μg/Kg	3/2/2012	ehernandez
3540C/8082A	Aroclor-1260	ND	68	μg/Kg	3/2/2012	ehernandez
3540C/8082A	Aroclor-1262	ND	68	μg/Kg	3/2/2012	ehernandez
3540C/8082A	Aroclor-1268	ND	68	μg/Kg	3/2/2012	ehernandez

Definitions:

ND - indicates that the analyte was not detected at the reporting limit

PESTICIDE/PCB ORGANICS ANALYSIS DATA SHEET

		Customer Sample#:	MB 1 4252 CU
Lab Name:	EMSL Analytical		
EMSL Sample ID:		Project:	
Lab File ID:	X17404.D	Sample Matrix:	Solid/Soil
Instrument ID:	ECD-X	Sampling Date:	12:00:00 AM
Analyst:	EH	Date Extracted:	3/1/2012
GC Column:	CLPest I (0.25 mm)	Analysis Date	3/5/2012 3:37:21 PM
GC Column 2:	CLPest II (0.25 mm)	Sample wt/vol:	10 G
% Moisture:	0	Dilution Factor:	1
PH:	0	Concentrated Extract Vol:	10 (mL)
GPC Cleanup(Y/N):	N	Injection Volume:	1 (ul)
Extraction Type:	3540C	Sulfur Cleanup:	N
Method:	SW846 8081/8082		

CAS NO	COMPOUND	Report Limit (mg/Kg)	CONC. (mg/Kg)	Q
12674-11-2	Aroclor 1016	0.050		U
11104-28-2	Aroclor 1221	0.050		U
11141-16-5	Aroclor 1232	0.050		U
53469-21-9	Aroclor 1242	0.050		Ū
12672-29-6	Aroclor 1248	0.050		U
11097-69-1	Aroclor 1254	0.050		U
11096-82-5	Aroclor 1260	0.050		U
37324-23-5	Aroclor 1262	0.050		U
11100-14-4	Aroclor 1268	0.050		U

Qualifier Definitions

U = Undetected

B = Compound detected in method blank

E = Estimated value

D = Dilution

P = Results between the two columns differ >40%

SOLID/ SOIL PESTICIDE/PCB LCS/QCS/ LFB RECOVERY

	Lab Name:	EMSL Analy	tical	Original File ID:	LCS 1 4252 X17404.D/X1	7405.D	
	* : Values outside of						
	COMPOUND	CAS NO	LOW LIMIT	HIGH LIMIT	SPIKE ADDED mg/Kg	LCS CONC. mg/Kg	LCS REC%
1	Aroclor 1016	12674-11-2	31	122	1.50	1.28	86
2	Aroclor 1260	11096-82-5	33	130	1.50	1.35	90
			L	Total Out			0 of 2

Printed: 03/06/12 09:48:26 AM SampleList: QC Batch 4252-1 ERM: T:\ERMs\8081-8082\8082soil.erm

SOLID/SOIL PESTICIDE/PCB MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

Lab Name:	EMSL Analytical		Original		0970-1 PCB	MS 8X						
			File ID:	,	X17408.D/X1	X17408.D/X17406.D/X17407.D	Q.70					
*: Values outside of				•								
COMPOUND	CAS NO	CAS NO LOW LIMIT	HIGH	RPD LIMIT	SAMPLE CONC.	MS SPIKE ADDED mg/Kg	MS CONC. ng/Kg	MS REC%	MSD SPIKE ADDED mg/Kg	MSD CONC. mg/Kg	MSD REC%	RPD %
Aroclor 1016	12674-11-2	12	164	25	00.00	3.54	3.15	68	3.55	3.15	88	0
Aroclor 1260	11096-82-5	43	167	25	00:00	3.54	2.90	82	3.55	2.84	80	2
			Total Out					0 of 2			0 of 2	0 of 2

PESTICIDE/PCB ORGANICS ANALYSIS DATA SHEET

		Customer Sample#:	MB 1 4253 CU
Lab Name:	EMSL Analytical		
EMSL Sample ID:		Project:	
Lab File ID:	X17391.D	Sample Matrix:	Solid/Soil
Instrument iD:	ECD-X	Sampling Date:	12:00:00 AM
Analyst:	EH	Date Extracted:	3/1/2012
GC Column:	CLPest I (0.25 mm)	Analysis Date	3/2/2012 6:14:20 PM
GC Column 2:	CLPest II (0.25 mm)	Sample wt/vol:	10 G
% Moisture:	0	Dilution Factor:	1
PH:	0	Concentrated Extract Vol:	10 (mL)
GPC Cleanup(Y/N):	N	Injection Volume:	1 (ul)
Extraction Type:	3550B	Sulfur Cleanup:	N
Extraction Type. Method:	SW846 8081/8082		

CAS NO	COMPOUND	Report Limit (ug/Kg)	CONC. (ug/Kg)	Q
12674-11-2	Aroclor 1016	50		U
11104-28-2	Aroclor 1221	50		U
11141-16-5	Aroclor 1232	50		U
53469-21-9	Aroclor 1242	50		U
12672-29-6	Aroclor 1248	50		U
11097-69-1	Aroclor 1254	50		U
	Aroclor 1260	50		U
11096-82-5		50		U
37324-23-5 11100-14-4	Aroclor 1262 Aroclor 1268	50	···	U

Qualifier Definitions

Printed: 03/05/12 12:08:07 PM SampleList: QC Batch 4253-1

ERM: T:\ERMs\8081-8082\8082soil.erm

U = Undetected

B = Compound detected in method blank

E = Estimated value

D = Dilution

P = Results between the two columns differ >40%

SOLID / SOIL PESTICIDE/PCB LCS/QCS/ LFB RECOVERY

	Lab Name:	EMSL Analy	tical	Original File ID:	LCS 1 4253 X17391.D/X1	7392 D	
	* : Values outside of				7(17001.5)7(1		
	COMPOUND	CAS NO	LOW LIMIT	HIGH LIMIT	SPIKE ADDED ug/Kg	LCS CONC. ug/Kg	LCS REC%
1	Aroclor 1016	12674-11-2	31	122	1500	1290	86
2	Aroclor 1260	11096-82-5	33	130	1500	1370	91
			J.,	Total Out			0 of 2

Printed: 03/05/12 12:24:48 PM SampleList: QC Batch 4253-1

ERM: T:\ERMs\8081-8082\8082soil.erm

SOLID/SOIL PESTICIDE/PCB MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

Lab Name:	EMSL Analytical		Original		0971-4 PCB	SW						
*: Values outside of			File ID:	. ,	X17395.D/X17393.D/X17394.D	7393.D/X173	394.D					
COMPOUND	CAS NO	CAS NO LOW LIMIT	HIGH	RPD LIMIT	SAMPLE CONC.	MS SPIKE ADDED ug/Kg	MS CONC. ug/Kg	MS REC%	MSD SPIKE ADDED	MSD CONC.	MSD REC%	RPD %
Aroclor 1016	40674440	3							ng/kg			
2000	1-20/4-11-7	12	164	25	0.00	2250	2200	86	2270	2070	2	
 Aroclor 1260	11096-82-5	43	167	30	6	OL CO			2	2010	9	
		?	ò		9.0	0077	2140	92	2270	2070	91	7
			Total Out					0.062			0	
								1		_		in to the

STANDARD OPERATING PROCEDURE FOR SAMPLING POROUS SURFACES FOR POLYCHLORINATED BIPHENYLS (PCBs)

The Office of Environmental Measurement and Evaluation EPA New England – Region 1 11 Technology Dr. North Chelmsford, MA 01863

Prepared by:	Dan Granz, Environmental Engineer	5/5/11 Date
Reviewed by:	Kim/Tisa, TSCA PCB Coordinator	5/5/11 Date
Reviewed by:	Jerry Keefe – EIA Team Leader	05/23/11 Date
Approved by:	Dan Boudreau, EIA Chemistry Team Leader	5/23/11 Date

<u>Disclaimer:</u> The controlled version of this document is the electronic version viewed on-line only. If this is a printed copy of the document, it is an uncontrolled version and may or may not be the version.

This document contains direction developed solely to provide internal guidance to U.S. Environmental Protection Agency (EPA) personnel. EPA retains the discretion to adopt approaches that differ from these procedures on a case by case basis. The procedures set forth do not create any rights, substantive or procedural, enforceable at law by a party to litigation with EPA or the United States.

Revision Page

Date	Rev#	Summary of Changes	Sections
12/97	1	Initial Approval, draft	
3/20/08	2	Major update, only for PCBs, added TSCA sampling	All sections
7/17/08	3	Disposal of dust filter and decon of vac hose	11.0 and 14.0
5/04/11	4	Vacuum Trap Design and Clean-out	9.4
			\

Table of Contents

1.0	Scope and Application4
2.0	Summary of Method4
3.0	Definitions4
4.0	Health and Safety Warnings5
5.0	Interferences
6.0	Personnel Qualifications6
7.0	Equipment and Supplies6
8.0	Sampling Design7
9.0	Sample Collection
10.0	Sample Handling, Preservation, and Storage
11.0	Decontamination11
12.0	Data and Record Management
13.0	Quality Control and Quality Assurance
14.0	Waste Management and Pollution Prevention
15.0	References
Attac	hments:

Example of Custody Seal and Sample Label

Example of Chain of Custody Form

1.0 Scope and Application

- 1.1 This Standard Operating Procedure (SOP) is suitable for collection of a porous matrix sample for analysis of Polychlorinated Biphenyls (PCBs).
- 1.2 This SOP describes sampling techniques for both hard and soft porous surfaces.
 - 1.2.1 Hard surfaces, and most soft surfaces, can be sampled using an impact hammer drill to generate a uniform, finely ground, powder to be extracted and analyzed for PCBs. This procedure is primarily geared at providing enough sample quantity for two analyses. Hard porous surfaces include concrete, brick, asphalt, cement, sandstone, limestone, unglazed ceramics, and other possible PCB suspected material. This procedure may also be used on other softer porous surfaces, such as wood.
 - 1.2.2 Soft surfaces can be sampled using a chisel or sharp knife to generate a representative sample to be extracted and analyzed for PCBs. Soft porous surfaces include wood, wall plasterboard, low density plastics, rubber, caulking, and other PCB suspected material.
- 1.3 This SOP provides for collection of surface samples (0 0.5 inches) and delineation of PCB contamination throughout the core of the porous surface. The procedure can be used to sample the porous surface at distinctly different depth zones.

2.0 Method Summary

A one-inch or other sized diameter carbide drill bit is used in a rotary impact hammer drill to generate a fine powder, or other representative sample, suitable for extraction and analysis of PCBs from porous surfaces. This method also allows the use of chisels or knives for the collection of samples from soft porous surfaces for PCB analysis.

3.0 Definitions

- 3.1 Field/Bottle Blank: A sample container of the same lot as the containers used for the environmental samples. This evaluates PCB contamination introduced from the sample container(s) from a common lot.
- 3.2 Equipment/Rinse/Rinsate Blanks: A sample that is collected by pouring hexane over the sample collection equipment after decontamination and before sample collection. The sample is collected in the appropriate sample container identical to the sample containers. This represents background contamination resulting from the field equipment, sampling procedure, sample container, and shipment.

- 3.3 Field Replicates/Duplicates: Two or more samples collected at the same sampling location. Field replicates should be samples collected side by side. Field replicates represent the precision of the whole method, site heterogeneity, field sampling, and the laboratory analysis.
- 3.4 Field Split Samples: Two or more representative subsamples taken from one environmental sample in the field. Prior to splitting, the environmental sample is homogenized to correct for sample heterogeneity that would adversely impact data comparability. Field split samples are usually analyzed by different laboratories (interlaboratory comparison) or by the same laboratory (intralaboratory comparison). Field splits are used to assess sample handling procedures from field to laboratory and laboratory comparability.
- 3.5 Laboratory Quality Samples: Additional samples that will be collected for the laboratory's quality control program: matrix spike, matrix spike duplicate, laboratory duplicates, etc.
- 3.6 Proficiency Testing (PT)/Performance Evaluation (PE) Sample: A sample, the composition of which is unknown to the laboratory or analyst, provided to the analyst or laboratory to assess the capability to produce results within acceptable criteria. This is optional depending on the data quality objectives. If possible, it is recommended that the PE sample be of similar matrix as the porous surface(s) being sampled.
- 3.7 Porous Surface: Any surface that allows PCBs to penetrate or pass into itself including, but not limited to, paint or coating on metal; corroded metal; fibrous glass or glass wool; unglazed ceramics; ceramics with porous glaze; porous building stone such as sandstone, travertine, limestone, or coral rock; low density plastics such as Styrofoam and low density polyethylene; coated (varnished or painted) or uncoated wood; painted or unpainted concrete or cement; plaster; plasterboard; wallboard; rubber; caulking; fiberboard; chipboard; asphalt; or tar paper.
- 3.8 Shipping Container Temperature Blank: A water sample that is transported to the laboratory to measure the temperature of the samples in the cooler.

4.0 Health and Safety

- 4.1 Eye, respiratory, and hearing protection are required at all times during sample drilling. A properly fitted respirator is required for hard porous surface sampling. A respirator is recommended whenever there is a risk of inhalation of either particulate or volatilized PCBs during sampling.
- 4.2 All proper personal protection clothing and equipment must be worn.

- 4.3 When working with potentially hazardous materials or situations, follow EPA, OSHA, and specific health or safety procedures.
- 4.4 Care must be exercised when using an electrical drill and sharp cutting objects.

5.0 Interferences and Potential Problems

- 5.1 This sampling technique produces a finely ground uniform powder, which minimizes the physical matrix effects from variations in the sample consistency (i.e., particle size, uniformity, homogeneity, and surface condition). Matrix spike analysis of a sample is highly recommended to monitor for any matrix related interferences.
- 5.2 Nitrile gloves are recommended. Latex gloves must not be used due to possible phthalate contamination.
- 5.3 Interferences may result from using contaminated equipment, solvents, reagents, sample containers, or sampling in a disturbed area. The drill bit must be decontaminated between samples. (see Section 11.0.)
- 5.4 Cross contamination problems can be eliminated or minimized through the use of dedicated sampling equipment.

6.0 Personnel Qualifications

- All field samplers working at hazardous materials/waste sites are required to take a 40 hour health and safety training course prior to engaging in any field activities. Subsequently, an 8 hour refresher health and safety course is required annually.
- 6.2 The field sampler should be trained by an experienced sampler before initiating this procedure.
- 6.3 All personnel shall be responsible for complying with all quality assurance/quality control requirements that pertain to their organizational/technical function.

7.0 Equipment and Supplies

7.1 This list varies with the matrix and if depth profiling is required

Rotary impact hammer variable speed drill 1-inch or other suitable (1/2, 3/4, etc.) diameter carbide tip drill bits Steel chisel or sharp cutting knife, and hammer Brush and cloths to clean area Stainless steel scoopulas

Aluminum foil to collect the powder sample

1 quart Cubitainer with the top cut out to collect the powder sample

Aluminum weighing pans to collect the powder sample

Cleaned glass container (2 oz or 40 mL) with Teflon lined cap

Decontamination supplies: hexane, two small buckets, a scrub brush, detergent, deionized water, hexane squirt bottle, and paper towels

Dedicated vacuum cleaner with a disposable filter or a vacuum pump with a dust filter Polyethylene tubing and Pasteur pipettes

Sample tags/labels, custody seals, and Chain-of-Custody form

8.0 Sampling Design

- 8.1 A sufficient number of samples must be collected to meet the data quality objectives of the project. If the source of the PCB contamination is regulated under the federal TSCA PCB Regulations at 40 CFR Part 761, the sampler should insure that the sampling design is sufficient to meet any investigation or verification sampling requirements. At a minimum, the following is recommended:
 - 8.1.1 Suspected stained area (s) should be sampled.
 - 8.1.2 At each separate location, collect at least 3 samples of each type of porous surface, regardless of the amount of each type of porous surface present.
 - 8.1.3 In areas where PCB equipment was used or where PCBs were stored, samples should be collected at a frequency of 1 sample/100 square feet (ft²).

9.0 Sample Collection

9.1 Hard Porous Surfaces

- 9.1.1 Lock a 1-inch or another size diameter carbide drill bit into the impact hammer drill and plug the drill into an appropriate power source. For easy identification, sample locations may be pre-marked using a marker or paint. (Note: the actual drilling point must not be marked.) Remove any debris with a clean brush or cloth prior to drilling. All sampling decisions of this nature should be noted in the sampling logbook.
- 9.1.2 Use a Cubitainer with the top cut off or aluminum foil to contain the powdered sample. Begin drilling in the designated location. Apply steady even pressure and let the drill do the work. Applying too much pressure will generate excessive heat and dull the drill bit prematurely. The drill will provide a finely ground powder that can be easily collected.

- 9.1.3 Samples should be collected at ½-inch depth intervals. Thus, the initial surface sample should be collected from 0 0.5 inches. A ½-inch deep hole generates about 10 grams (20 mL) of powder. Multiple holes located closely adjacent to each other, may be needed to generate sufficient sample volumes for a PCB determination. It is strongly recommended that the analytical laboratory be consulted on the minimum sample size needed for PCB extraction and analysis.
- 9.1.4 Wall and Ceiling Sampling: A team of two samplers will be required for wall and ceiling sampling. The second person will hold a clean catch surface (e.g. an aluminum pan) below the drill to collect the falling powder. Alternatively, use the chuck-end of the drill bit and punch a hole through the center of the collection pan. The drill bit is then mounted through the pan and into the drill. For ceilings, the drill may be held at an angle to collect the powder. Thus the driller can be drilling at an angle while the assistant steadies the pan to catch the falling powder. As a precaution, it may be advantageous to tape a piece of plastic around the drill, just below the chuck, to avoid dust contaminating the body of the drill and entering the drill's cooling vents. Caution must be taken to prevent obstruction of the drill's cooling vents.

9.2 Soft Porous Surfaces

- 9.2.1 The procedure for the hard porous surface may be used for certain soft porous surfaces, such as wood.
- 9.2.2 Samples should be collected at no more than $\frac{1}{2}$ -inch depth intervals using a metal chisel or sharp cutting knife. Thus, the initial surface sample should be collected from 0-0.5 inches. It is important to collect at least 10 grams for analysis.
- 9.2.3 For soft porous surfaces, such as caulking and rubber, a representative sample can be collected using a metal chisel or sharp cutting knife.

9.3 Multiple Depth Sampling


- 9.3.1 Multiple Depth Sampling may not be applicable to certain porous surfaces, such as caulking.
- 9.3.2 Collect the surface sample as outlined in Section 9.1 or 9.2.
- 9.3.3 Use the vacuum pump or cleaner to clean out the hole.
- 9.3.4 To collect multiple depths there are two options.

- 9.3.4.1 Option one: drill sequentially ½-inch increments with the 1 inch drill.
- 9.3.4.2 Option two: drill with the 1 inch bit and either make the hole larger or use a smaller bit to take the next ½- inch sample.
- 9.3.5 A stainless steel scoopula will make it easier to collect the sample from the bottom of the hole.

9.4 Vacuum Trap Design and Clean-out

The trap presented in Figure 1 is a convenient and thorough way for collecting and removing concrete powder from drilled holes. The trap system is designed to allow for control of the suction from the vacuum pump and easy trap clean-out between samples. Note, by placing a hole in the inlet tube (see Figure 1), a finger on the hand holding the trap can be used to control the suction at the sampling tip. Thus, when this hole is left completely open, there will be no suction, and the sampler can have complete control over where and what to sample. To change-out between samples the following steps should be taken: 1) the Pasteur pipette and piece of polyethylene tubing at the sample inlet should be replaced with new materials, 2) the portion of the rubber stopper and glass tubing that was in the trap should be wiped down with a clean damp paper towel (wetted with deionized water) and then dried with a fresh paper towel, 3) a clean pipe cleaner should be drawn through the glass inlet tube to remove any concrete dust present, and 4) the glass tube or flask used to collect the sample should swapped out with a clean decontaminated sample trap. Having several clean tubes or flasks on hand will facilitate change-out between samples.

Figure 1



Note: the holes should be vacuumed thoroughly to minimize any cross-contamination between sample depths and the bits should be decontaminated between samples. (See Section 11.0)

10.0 Sample Handling, Preservation, and Storage

- 10.1 Samples must be collected in glass containers for PCB analyses. In general, a 2-ounce sample container with a Teflon-lined cap (wide-mouth jars are preferred) will hold sufficient mass for most analyses. A 2-ounce jar can hold roughly 90 grams of sample.
- 10.2 Samples are to be shipped refrigerated and maintained at \leq 6°C until the time of extraction and analysis.
- 10.3 The suggested holding time for PCB samples is 14 days to extraction.

11.0 Decontamination

- 11.1 Assemble two decontamination buckets. The first bucket contains a detergent and potable water solution, and the second bucket is for rinsate. Place all used drill bits, hose for the vacuum cleaner, and utensils in the detergent and water bucket. Scrub each piece thoroughly using the scrub brush. Note, the powder does cling to the metal surfaces, so care should be taken during this step, especially with the twists and curves of the drill bits. Next, rinse each piece with water and hexane. Place the rinsed pieces on clean paper towels and individually dry and inspect each piece. Note: all pieces should be dry prior to reuse.
- 11.2 Lightly contaminated drill bits and utensils may be wiped with a hexane soaked cloth and hexane rinsed for decontamination.

12.0 Data and Record Management

- 12.1 All data and information collection should follow a Field Data Management SOP or Quality Assurance Project Plan (QAPP).
- 12.2 Follow the chain of custody procedures to release the samples to the laboratory. A copy is kept with the sampling records.
- 12.3 The field data is stored for at least 3 years.

13.0 Quality Control and Quality Assurance

- 13.1 Representative samples are required. The sampler will evaluate the site specific conditions to assure the sample will be representative.
- 13.2 All sampling equipment must be decontaminated prior to use and between each discrete sample.
- 13.3 All field Quality Control (QC) sample requirements in a Sample and Analysis Plan (SAP) or QAPP must be followed. The SAP or QAPP may involve field blanks, equipment blanks, field duplicates and/or the collection of extra samples for the laboratory's quality control program.
- 13.4 Field duplicates should be collected at a minimum frequency of 1 per 20 samples or 1 per non-related porous matrix, whichever is greater.

14.0 Waste Management and Pollution Prevention

14.1 During field sampling events there may be PCB and/or hazardous waste produced from the sample collection. The waste must be handled and disposed of in accordance with federal, state, and local regulations. The dust filter, and tubing if a vacuum pump is used, is disposed after each site investigation. This waste will be treated as PCB waste if the samples are positive for PCBs. It may be possible to manage or dispose of the waste produced at the site where the work was performed. If the site does not meet regulatory requirements for these types of activities, the waste must be transported to a facility permitted to manage and/or dispose of the waste.

15.0 References

- 1. <u>Guidance for the Preparation of Standard Operating Procedures for Quality-Related Operations</u>, QA/G-6, EPA/600/R-96/027, November 1995.
- 2. 40 CFR Part 761 Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution In Commerce, and Use Prohibitions
- 3. Sample Container and Holding Time: RCRA SW 846, Chapter 4, Table 4.1, Revision 4, February, 2007.

Example of Sample Label and Custody Seal

VIRONMENTAL PROTECTION AGENCY OFFICIAL SAMPLE SEAL	SIGNATURE			SEAL BROKEN	
UNITED STATES					
UNITED STATES	SAMPLE NO.		DATE	¥B⊀	
S		SAMPLING CREW(FIRST, INITIAL, LAST NAME) SAMPLE NO.	ANALYSIS SAMPLE NO.	SAMPLING CREW(FIRST, INITIAL, LAST NAME) AMOUNT ANALYSIS SAMPLE NO. DATE	SAMPLING CREW(FIRST, INITIAL, LAST NAME) ANALYSIS SAMPLE NO. DATE

Example of Chain of Custody Form

Relinquished by: (Signeture) Relinquished by: (Signeture)	elinguished by: /Signatu			SAMPLERS: (Sgnsture)	PROJ. NO. PROJECT NAME
(6)		76		DMP.	1 CT NA
			GI	RAB	£
Date	Date	Date			
Date / Time	/Time	Date / Time		STATI	
Received for Laboratory by:	Received by: (Signatura)	Received by: (Signature)		CC TAION LOCATION	CHAIN OF
				OF CON- TAINERS	CUST
Date / Time	Relinquished by: (Signature)	Relinquished by: (Signatura)			CHAIN OF CUSTODY RECORD
Remarks	tura)	ture)			
	Date	Date			
	Date / Time	Date /Time			
	Received by: (Signature)	Received by: (Signature)		REMARKS	